UNCLASSIFIED

AD 404943

DEFENSE DOCUMENTATION CENTER

FOR

SCIENTIFIC AND TECHNICAL INFORMATION

CAMERON STATION, ALEXANDRIA VIRGINIA



UNCLASSIFIED


MOTICE: When government or other drawings, specifications or other data are used for any purpose other than in connection with a definitely related government procurement operation, the U. S. Government thereby incurs no responsibility, nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

JPRS: 18,780

OTS: 63-21611

18 April 1963

FOR REFERENCE ONLY AT EACH OF THE DOC OFFICES. THIS REPORT CANNOT BE SATISFACTORILY REPRODUCED, DDC DOES NOT FURNISH COPIES



TISIA

U. S. DRPARTMENT OF COMMERCE

OFFICE OF TECHNICAL SERVICES

JOINT PUBLICATIONS RESEARCH SERVICE

Building T-30

Ohio Dr. and Independence Ave., S.W. Washington 25, D. C.

Price: \$1.75

FOREWORD

Millerton to

This publication was prepared under contract for the Joint Publications Research Service as a translation or foreign-language research service to the various federal government departments.

The contents of this material in no way represent the policies, views or attitudes of the U. S. Government or of the parties to any distribution arrangement.

PROCUREMENT OF JPRS REPORTS

All JPRS reports may be ordered from the Office of Technical Services. Reports published prior to 1 February 1963 can be provided, for the most part, only in photocopy (xerox). Those published after 1 February 1963 will be provided in printed form.

Details on special subscription arrangements for JPRS social science reports will be provided upon request.

No cumulative subject index or catalog of all JPRS reports has been compiled.

All JPRS reports are listed in the Monthly Catalog of U. S. Government Publications, available on subscription at \$4.50 per year (\$6.00 foreign), including an annual index, from the Superintendent of Documents, U. S. Government Printing Office, Washington 25, D. C.

All JPRS scientific and technical reports are cataloged and subject-indexed in <u>Technical Translations</u>, published semimonthly by the Office of Technical Services, and also available on subscription (\$12.00 per year domestic, \$16.00 foreign) from the Superintendent of Documents. Semiannual indexes to <u>Technical Translations</u> are available at additional cost.

State of the

JPRS: 18,780

ABSTRACTS PERTAINING TO COMMUNIST CHIMA IN SOVIET ABSTRACTS JOURNALS

No 56

(Mechanics Series)

This serial publication contains translations of abstracts pertaining to Communist China published in Referetiveny Zhurnel. Nekhanika (Soviet Abstracts Journal, Mechanics Series), Nos 1, 2, 3, 4, 5, 6, 7, 9, 18, 11 and 12, 1962.

Table of Contents

•	PAR
No 1, 1962	
General Mechanics	• 1
Hydromechanics. Movement of Liquid and Gas Mixtures	1
Rydromechanics. Dynamic meteorology	2
Hydromechanics. Movement of Liquids and Gases in Porous Media	3
Elasticity and Plasticity. Theory of Elasticity	. 5
No 2, 1962	
General Machanics	, 8

l .	Page
* Bydromeonanics. Acoustics	10
Hydromechanics. Hydrodynamics and Hydraulics	10
Hydromechanics. General Theory of Movement of Viscous Liquids	11
No 3, 1962	
General Mechanics	12
Redromachumies. Dynamics of Gases and Aerodynamics	13
Hydremechanics. Hydrodynamics and Hydraulics	15
Hydromechanics. Heat Transfer	17
Aydromachanics. Dynamic Heteorology	18
Hydromechanics. Movement of Liquid and Gas Mixtures	20
Elasticity and Plasticity. Ground Mechanics	21
Masticity and Plasticity. Rods and Rod Systems	22
No. 4. 1962	
Hydromechanics. Movement of Liquids and Gases in Poreus Hediagrams as a second control of the Co	23
Elasticity and Plasticity. Rods and Rod System	24
Elasticity and Plasticity. Strength of Constructions	25
No 5. 1962	
General Mechanics	26
Winnesharing Transmiss of Comes and Laradynesics	27

· r

.

	page
Hydromechanics. Movement of Liquid and Gas Mixtures	29
Hydromechanics. Movement of Liquids and Gases in Porous Media	29
Elasticity and Plasticity	30
No 6. 1962	
General Mechanics. Theory of Mechanisms and Machines	34
Hydromechanics. Dynamics of Gases and Aerodynamics	34
Hydromechanics. Dynamic Meteorology	35
Elasticity and Plasticity	36
No 7, 1962	
General Mechanics	37
Elasticity and Plasticity	37
Hydrodynamics and Rydraulics	38
Dynamic Neteorology	39
Elasticity and Plasticity	39
Hydromechanics	40
Strength of Materials	40
General Mechanics	42
Movements of Liquids and Cases in Porous Media	43
Elasticity and Plasticity	h.
Plackicity, Green, Soil Machanias	hh

_	
No 10, 1362	<u>Page</u>
Theory of Mechanisms and Machines	46
Tydromechanies	46
No 11, 1962	
General Machanics	49
Magnetohydremlies	50
Gas Bymarics.and.Assodynamics	50
Nydromechanics	51
Elasticity Theory	5 4 ·
Elasticity and Flasticity	54
Plasticity, Greep, Soil Mechanics	55
Stability of Constructions	55
No 12, 1962	
Hydromechanics. Boundary Layer	56
Eydromechanics	57
Elasticity Theory	59
Elasticity and Plasticity	60
Plasticity, Greep, Soil Mechanics	60
Elasticity and Plasticity	61

RZh Mekhanika 1-62

Ť,

Abst#IAlll Mechanics/General Mechanics

TOLSTOY, D. M. KAPIAN, R. L. LIN Fu-shang P'AN Pin-yao

New Experimental Data on External Friction

Issled. v obl. poverkhnostn. sil (Investigations in the Field of Surface Forces) Moscow, Academy of Sciences USSR, 1961, pp 126-138

[No abstract]

1/1

RZh Mekhanika

Abst#1B744 Mechanics/Movement of Liquid and Gas Mixtures

WU Ch'uan-yao TAI Chia-yun CHIANG Chi-kuang YANG Heiso-ban TING Heisng-yu

Determination of the Flow Velocity of Water in Settling Tanks

Sichuan daxue xuebao. Ziran kexus, Acta scient. natur. Univ. ssechuan 1958 No 2, pp 33-35

[No abstract]

RZh Mekhanika

Abst#18663 Mechanics/Hydromechanics/Dynamic Meteorology

HSU Heiso-chin

Determination of the Wind while Taking into Consideration Monlinear Terms of Acceleration and Interior Friction Depending on Altitude (Stationary problem)

Vestn. Mosk un-ta Fizastron. Herald of the Moscow University. Physics and Astronomy. 1960. No 1, pp 48-57

Given is the distribution of the wind in ratio to height in the surface layer in the presence of eddy friction and acceleration (without local derivative). A two-layer problem is investigated. The model of M. I. Yudik and Shvets is used for changing the friction coefficient by the change of the height. The conditions for the concordance of the velocities and their derivatives are used at z = h, where h is the height of the layer near the earth, a further condition is that of the adherence of the air to the earth's surface and the limitedness of the velocity to infinity. The problem leads to an integral-differential equation which is solved by successive ap-

Abst#18663 (cont'd)

proximations. As first approximation serves the solution of the equation of the even movement for turbulent atmosphere without taking into account the acceleration. Then, the distribution of the wind in height takes place in the second approximation by taking into account the convective part of the acceleration. Tables and graphs are shown in relation to the change of the wind in ratio to height for different values of the parameters. Nine references.

K. Reshetnikova

RZh Mekbanika 1-62

Abet#1B667 Mechanics/

. a Movement of Liquids and Guses in Porous Media/ Unestablished Move-

IANG Chai-hain

ments.

Approximation Method of the Solution of One-Dimensional Nonstationary Gas Filtration

Tr. Mosk in-t neftekhim, i gaz, prom-sti (Proceedings of the Moscow Institute of the Naphtachemistry and Gasindustry) Issue 33, pp 282-289

The integral relation method is used for the radial problem of nonetacionary gas leakage in case of continuous output of gas, while the relation of the pressure p to the distance r from the well is thus expressed: $p^{2}(r,t) = p_{1}(t) \ln \frac{r}{I(t)} + p_{2}(t) + p_{3}(t) \frac{r}{I(t)}$

where $p_1(t)$, $p_2(t)$, $p_3(t)$ are coefficients to be determined while 1(t) is the radius of the conditional influence limit. The results obtained by above-suggested method tally with the figures obtained by computers. By analogy one can solve the radial problem by cosincidal law for the change of width. As shown by further numerical 1/2

Abat#1B867 (cont'd)

analysis pressure drop on the periphery reveals itself in the given case as coming near to the pressure drop on the periphery of an equidimensional stratum of constant thickness.

V. Shestakov

RZh Mekhanika 1-62

Abst#1E371 Mechanics/

IANG Chai-hsin

Movement of Liquids and Gases in Porous Media / Unestablished Movements.

Approximation Method of the Solution of the Problem of Nonstationary Gas Filtration in a Circular Stratum

Tr. Mosk. in-t neftekhim, i gaz, prom-sti (Proceedings of the Moscow Institute of the Naphtachemistry and Gasindustry) Issue 33, pp 252-262

In order to solve the one-dimensional unsettled gas leakage in case of isotropic flow, the nonlinear differential equation (of the Bussinesk equation type for ground stream) is solved by the integral relation method introduced in the theory on leakage by G. I. Barenblatt. In order to determine the elements of the leaking stream in a semilimited and closed rectilinear layer the pressure square is represented in ratio to the distance as a polynomial of second degree. Whereupon use is made of only one balanced integral relation. The solution for the semilimited layer thus obtained is compared with the strict solution of P. Ya. Polubarinova-Kochina whereby the results tallied in a satisfactory way. Five references.

1/1

1-62

RZh Mekhanika

Abst#1B882 Mechanics/

. Movement of Liquids and Gases in Porous Media ./ Unestablished Movements

LI Yung-shang

Method to Establish the Piezoconductivity of Layers at the Point of Maximum Pressure Change of the Layer in the Reacting Well

Tr. Mosk, in-t neftekhim.i gaz, prom-sti (Proceedings of the Moscow Institute of Naphtachemistry and Gasindustry) 1961, issue 33, pp 249-251

The curve of the pressure changes in the reacting well is measured at a temporal change of the yield in the perturbed well. The piezoconductivity & is determined through the following formula

$$x = \frac{r^2 t_1}{4t_2 (t_1 + t_2) \ln \frac{t_1 + t_2}{t_2}} .$$

the starting moment is to in which the pressure change reaches its maximum (or minimum), with definite distances r of the well's and 1/2

Abst#18882 (cout'd)

known spaces of time of the perturbations to . .

G. Taybul'skiy

2/2

RZb Mekbanika 1-62 Abst#10111 Mechanics/Elasticity and Plasticity/ Theory of Elasticity

CHENG K'e-yang

Plane Viorations of Foundations

Izy, yyash uchebn, zavedeniy. Str-vo i arkhitekt. (News of Higher Educational Institutions. Construction and Architecture) 1959, No 9, pp 71-78

Here are investigated the free and positive plane vibrations of a solid body becoming quiescent on account of the elasticity of the base. The elastic basis (elastic according to Winkler) has different yielding under pressure in different directions perpendicular to each other and under bending. In order to solve the problem a system of three canonical equations is set up, whose coefficients are established through formulae obtained previously (cf. Kiselev V. A. Beams and Frames) by the elasticity of the base. The general solution is specified for the location of the centre of mass in several particular cases and for the point of application of the force. The frequencies of the free vibration and the amplitudes of the positive vibrations

Abst#Rull (cont'd)

are determined for a double-stage compressor mounted on base.

E. Beylin

2/2

RZh Mekhanika 1-62 Abst#10116 Mechanics/Klasticity and Plasticity/ Theory of Elasticity

HSINH Tsu-wei

Matural Vibrations of the Double-Einged Parabolical Arch at the Joint Strain of the Superposed Construction

Stroit, mekhan, i reschet scoruzh. (Structural Mechanics and Computation of the Construction) 1960, No 3, pp 34-39

The method suggested by A. T. Smirnov (Stability and Vibrations of Constructions, Moscow, Transchelgorizdat 1958 - RZhMekh 1959, No 11, 14107) is employed, based on the theory of matrices. The supports are supposed to be hinged to the beam and arch, the curve of the axes of the arch is substituted by a broken one, while the masses are applied on the ends of the square sections. The superfluous hyperstatic unknown, undetermined values are substituted by stresses in the supports. One studies the first skew symmetric form of the system's vibrations. The relations are composed in the matrix system making it possibile to find the natural frequency of the vibrations and the critical thrusts; being aware of whom one knows how to appraise the influence on the

Abst#10116 (cont'd)

frequency of the normal forces in the arch. A numeric example is shown for a parabolical arch. The result concerning a large groups of arches is presented under different rigidity conditions of the beam and arch and in respect to different heights of the arch.

I. Snitko

2/2

7

NZh Mekhanika 2-62

Abst#2A125 Mechanics/ General Mechanics/ Control Theory

NOR-RAMENSKIY, A. E. BUNG Chier

Optimum Tracking Device with Two Controlling Parameters

Avtomatika 1 telemekhanika (Automation and Telemechanics) 1961, 22, No 2, pp 157-170

The task is investigated how to design a tracking device with preset limits of change and two controlling parameters being an optimum construction for rapid action.

The parameters of the electrical device are chosen on the basis of L. S. Pontriyagin's maximum. The author expounds the means how to realize the law on the change of the controlling parameters, presents the description of the construction layout and the devices carrying into effect that layout.

The obtained results are shown by graphs and pictures; further 1/2

hbut#2A125 (cont'd)

the operation of the tracking device is presented in comparison with other possible controls.

N. Apykhtin

RZh Mekhanika 2-62 Abst#2A170 Mechanics/General Mechanics/ Theory of Mechanisms and Machines

SHU Sung-k'wai

Problems on the Stability and Monlinear Oscillations in Systems of Multistage Salsyns

Shu-haush haush-pao, Acta math. sinica 1961, 11, No 2, pp 170-180.

[No abstract]

1/1

RZh Mekhanika 2-62 Abst#2A200K Mechanics/General Mechanics/ Theory of Mechanisms and Machines

HUANG Wei-te

The Vibration of Engines

Shanghai, Shanghai k'o-hsush chi-shu ch'u-pan-she 1960, 180 thousand characters.

[No abstract]

RZb Mekhanika

Abst#2B99 Mechanics/Hydromechanics/ Acoustics

FENG Shao-sung

Reflection of a Wave with Finite Amplitude

Akast.Zh. (Nournal of Acoustics) 1960, 6, No 4, pp 491-493

The problem of the reflection of a wave incident on a wall at an angle of 45° is solved in case of an ideal gas by the method of subsequent accurate approximations including the second approximation. It is proved that in case of a reflection at such angle a double frequency wave comes into being, whose amplitude increases by the distance, while the reflection itself takes place according to the laws valid for infinite small amplitudes. Besides that, a double frequency wave comes into being, cylindrically symmetric with the amplitude, not changing with distance.

V. Krasil'nikov

1/1

RZh Mekhanika 2-62 Abst#2B332 Mechanics/Hydromechanics/Hydrodynamics and Hydraulics

SHEW Tsun-p'ing

A Contribution to the Determination of the Elements of the Internal Waves in the Sea from Single Hydrological Observations

Izv. AN SSSR series Geofizika

(News of the Academy of Sciences USSR Geophysical Series, 1961, No 7, pp 1006-1091

[No abstract]

RZh Mekhanika 2-62 Abst#25475 Mechanics/ Hydromechanics/ General Theory of Movement of Viscous Liquids

SHI Tsung-pao VANO Kwang-yin

Contribution to the Theory of the Movement of Viscous Liquids

Shu-haush haush-mao. Acta math. sinica 1961, 11, No 1, pp. 1-10.

[No abstract]

1 /1	
urda	et en

NZh Mekhanika 3-62 Abst/3All4 Mechanics/General Mechanics

CHANG Yung-aba LI K'un-yuan WANG Mu-ah'iu

Stability of Novement in a Finite Time Range

simeholith Hough-pas Acts math sinion 1961, 11 No 2, pp 141-150

The stability of the following system is investigated in a finite system

$$\frac{dx_l}{dt} = p_{l_1}(t)x_1 + \ldots + p_{l_n}(t)x_n \ (l=1,\ldots,n)$$

and

$$\frac{dx}{dt} = p_{i1}(f)x_1 + \ldots + p_{in}(f)x_n + X_i + R_i$$

where

 $R_{i}(x_{1},\ldots,x_{n}) = \delta \rho_{i}(x_{1}+\ldots+\delta \rho_{i}(x_{n}+\delta x_{i}))$

The authors have obtained several interesting conditions of stability by making use of the Lyapunov function of following form:

7/3

Abst#3All4 (cont'd)

$$V = q^{2} (f) \sum_{l_{1}, k=1}^{n} \beta_{lk} x_{l} x_{k} =$$

$$= q^{2} (f) \left[\Delta_{2} \dots \Delta_{n} \sum_{j=1}^{n} x_{j}^{2} + \sum_{e=1}^{n-1} \sum_{j=1}^{n} \prod_{\substack{e \neq e \neq 1 \\ e \neq e}}^{n} \Delta_{e} \times \Delta_{e}^{2} (f; x_{1}, \dots, x_{n}) \right]$$

where $\varphi(t) \geqslant \delta > 0; \Delta_1, \dots, \Delta_n$ is the essence of the Hurwitz determinant of the characterizing equation

$$||\rho_{ij}(t) - \lambda f_{ij}|| = (-1)^n (\lambda^n + \rho_1 \lambda^{n-1} + \dots + \rho_n) = 0$$

 $A_{n,i}(t;\,x_1,\,\ldots,\,x_n)$ are the determinants obtained from A_n through substitution of all the elements of the p_{k-1} s-M line by the values

EM' where My wis a determinant of the k-th order whose

elements are in essence the elements of the γ_1,\ldots,γ_r columns and γ_1,\ldots,γ_r is a line of the $(\gamma_1,\ldots,\gamma_r)$ determinant obtained from

hp, (t) | through substitution of the j-th column by 2/3

Abst#3All4 (cont'd)

the symbol $\sum M_{v_1, \dots, v_K}^{(l)}$ denotes the total of all $M_{v_1, \dots, v_K}^{(l)}$

in relation to γ_{-} , where γ_{-} , where γ_{-} is in essence every kind of combinations of the numbers 1, ..., n, where the number j is included in $(\gamma_{-}$, γ_{-}) without fail.

Chang Te-chiang

3/3

RZh Mekhanika 3-62: Abst#3Bl36 Mechanics/ Hydromechanics/ Dynamics of Gases and Aerodynamics

LIN Chien-ping

Some Frankl Tasks

Yestn.Leningr.um-ta (News of the Leningrad University) 1961, No 13, pp 28-39 (English summary)

A theorem on the uniqueness of a quasiregular solution of the following task of F. U. Frankl is demonstrated

$$K(y) u_{yy} + u_{yy} = 0, K(y) y > 0, K'(y) > 0$$

$$u|_{BA} = \Phi_1(x), u|_{CB} = \psi_1(x), u|_{AA'} = 0$$

$$u(0, y) = u(0, -y) = f(y), -1 < y < 1$$
(1)

where BA is a Jordan curve, A'C, CP are the characteristics (see Figure) in the assumption


$$K(y) + K(-y) > 0, 0 < y < 1$$

$$(x-m) \frac{dy}{ds} + y \frac{dx}{ds} < 0 \text{ He BA, } m > \max_{A} (x). \tag{2}$$

-1/3

Abet#3B136 (cont'd)

Condition (2) is satisfied in case of the gasodynamic equation of Chaplygin. Two new mutually conjugated tasks deriving from the task of Frankl are also stated



Task 1. Work out the solution of equation (1) satisfying the limit conditions

$$u_{1BAA} = \psi_{1}(a), u_{1}|_{CB} = \psi_{2}(a)$$

$$u_{2}(0, y) = u_{2}(0, -y) = f(y), -1 < y < 1$$

Task 2. Work out the solution of equation (1) satisfying the limit

Abet#38136 (cont'd)

conditions

$$|u_x|_{BA} = \psi_1(s), \ u|_{A^*C} = \psi_2(s), \ u_y|_{CB} = \psi_1(s)$$

$$K(y) u_x(0, y) + K(-y) u_x(0, -y) = f(y), \ -1 < y < 1$$

Theorems are demonstrated on the uniqueness of the regular solutions and existence of generalised solutions with a method analogous to that used in the work of Morawets (Morawets C. S. Communs Pure and Appl Math 1958, 11, No 3, pp 315-331).

P. Barantsev

RZh Mekhanika 3-62 Abst#3B455 Mechanics/Hydromechanics / Hydrodynamics and Hydraulics

LIU Ta-ming

Distribution of Velocities and Pressures in the Spillways of Combined Rydroelectrical Power Plants

Gidrotekhn.stro-vo (Hydrotechnic Construction) 1961, No 8, pp 45-48

An equation is deduced to determine the value of pressure in any waterflow within the extent of the curvilinear sections of combined GES [Gidroelektricheskaya stantsiya; Hydroelectric Power Plant] according to definite geometrical parameters and definite values of the full specific energy of the flow before the overflow weir. Based on the conclusion of the equation a conjecture is proposed corroborated by experimental data, i. e., the distribution of the velocities in the curvilinear sections of the overflow weir is subject to the law of spaces. The experimental figures characterising the distribution of pressures along the length of the overflow weirs is presented and suggestions are offered for their general design.

1/1

34

V. Gromov

RZh Mekhanika 3-62 Abst#3B514 Mechanics/ Hydromechanics/ Hydrodynamics and Hydraulics

CH'EN Chen-ch'eng

The Hydrodynamic Pressure on the Dam Caused by its Aperiodic or Inpulsive Oscillations and the Vertical Oscillations of the Soil Surface

Prikl, matem, i mekhan (Applied Mathematics and Mechanics) 1961, 25, mp 716-728

The task of determining the dynamic pressure of the fluid on the dam is investigated. The pressure is caused by the speriodic and impulsive oscillations of the dam itself and by the vertical oscillations of the soil surface above the fluid.

Accordingly, the dam and the seil surface are located in the planes $x = U_1(t)$ and $y = U_2(t)-h$, while the area $x > U_1(t)$, $U_2(t)-h < < y < U_2(t)$, $-\infty < z < +\infty$ is filled with the fluid.

The potential $\varphi(x, y, t)$ of the velocities of the fluid satisfies in the area $x > U_1(t)$, $U_2(t)-h < y < U_2(t)$ a Laplace equation, -1/3

Abst#3B514 (cont'd)

the initial conditions

$$\frac{\partial \varphi\left(x, 0, 0\right)}{\partial t} = 0, \quad \frac{\partial \varphi\left(0, y, 0\right)}{\partial x} = V_{1}\left(0\right)$$

$$\frac{\partial \varphi\left(x, -h, 0\right)}{\partial y} = V_{2}\left(0\right)$$

and the conditions on the limit of the area

$$\frac{\partial \Phi}{\partial x} = V_1(t) \quad \text{if} \quad x = U_1(t)$$

$$\frac{\partial \Phi}{\partial y} = V_2(t) \quad \text{if} \quad y = U_2(t) - h$$

$$\frac{\partial^2 \Phi}{\partial t^2} + g \frac{\partial \Phi}{\partial y} = 0 \quad \text{if} \quad y = U_2(t)$$

Here $V_1(t)$ and $V_2(t)$ are the corresponding velocities of the oscillating dam and soil surface, while $U_1(t)$ and $U_2(t)$ are their displacements. The free surface of the fluid is assumed to be known previously and conjectured to be deformed exactly like the soil surface.

The searched solution is a Fourier integral. The arbitrary functions entering in the solution are determined by the initial and limit conditions. Formulae are deduced bearing on the distribution of the

' Abst#3B514 (cont'd)

Confidence

dynamic pressure of the fluid on the dam. It follows from the results obtained that the vertical oscillations of the soil surface have a considerable influence on the load of the dam in case of destretive as well as violent earthquake.

Z. Dobrovolskaya

RZh Mekhanika

Abst#3B584 Mechanics/Hydromechanics/Heat Transfer

TS'AI K'uo-en

Heat Exchange in a Turbulent Flow of Fluid with High Values of the Prandtl Numbers

Ingh. fiz. zh. (Engineering Physical Journal) 1961, 4, No 8, pp 20-29

The theoretical investigation of the heat exchange in a turbulent flow of fluid with high Prandtl'numbers is based on the perfection of the semiempirical theory of turbulence created by L. G. Loytsyanskiy (Prikl matem i mekh; Applied Mathematics and Mechanics 1960, 24. No 4, pp637-646). Meanwhile in order to obtain a relatively simple and obvious solution the author -- unlike L. G. Loytsanskiy -- developes the stream in "o domains. The first domain comprises the so-called "laminar" and intermediate domain." But, unlike Karman and Prandtl, author takes into account all-over this domain the interaction of a molecular and turbulent transfer needed for the relatively high Frandtl numbers. Author succeeds to obtain for this domain an uninterrupted

Abst#3B584 (cont'd)

solution of closed form. The second domain contains the turbulent core, in which one can disregard the molecular transfer. In this domain the usual logarithmic velocity distribution and corresponding logarithmic temperature distribution may be used.

Author uses for obtaining the expression of temperature distribution the concept of "The Prandtl Turbulence Number" $G = \xi_{q}/\xi_{z}$ which one may assume for the first domain as equal to 0.8 according to the experimental data of Deissler (Deissler R. NASA Rept. 1955, No 1210, 14 pp - RZEMekh 1960, No 8, 10401).

Author has obtained relatively cumbersome expressions in universal coordinates for the velocity and temperature profiles. The curve of the velocity profile tallies well with the experimental figures. Besides that author has obtained an expression for Stanton's number, also cumbersome enough. It becomes somehow more simple for higher Prendtl numbers. The formulae obtained tally well with Deissler's experiments.

2/2

E. Kalinin

RZh Mekhanika

Abst#3B704 Mechanics/Hydromechanics/Dynamic Meteorology

CEU Yun-t'1

Computation of the Dynamic Influence of Mountain Ranges in the Ronlinear Task of Long-term Forecast of Meteorologic Elements

Izv.AN SSSR ser.geofiz. (News of the Academy of Sciences USSR Geophysical Series) 1959, No 12, pp 1807-1820

Generalization of E. N. Blinova's work (Reports of the AN USSR 1956, 110, No 6) on the influence of mountain ranges on nonstationary atmospheric processes on planetary scale. Following are the equations taken as starting points:

$$\frac{\partial \Omega}{\partial t} + \frac{\upsilon}{u} \frac{\partial}{\partial \theta} (\Omega + 2\omega \cos \theta) + \frac{u}{a \sin \theta} \frac{\partial \Omega}{\partial \lambda} - \frac{R}{a^{2} \sin \theta} \left(\frac{\rho'}{\overline{\rho}}, T' \right) + \frac{2\omega \cos \theta + \Omega}{\overline{\rho}} \frac{\partial \overline{\rho} w}{\partial z}$$
(1)
$$\frac{\partial T'}{\partial t} + \frac{\upsilon}{u} \frac{\partial T'}{\partial \theta} + \frac{u}{a \sin \theta} \frac{\partial T'}{\partial \lambda} + (\gamma_{e} - \gamma)w = 0$$
(2)

1/4

Abst#3B704 (cont'd) Here
$$2 = \frac{1}{a \sin \theta} \left[\frac{\partial}{\partial \theta} (u \sin \theta) - \frac{\partial v}{\partial \lambda} \right]$$

is the vertical component of the vortex of velocity, a is the medium radius of the earth, θ is the latitudinal complement, λ is the longitude, u, v, we are the components of the vector of wind velocity along the axes λ , θ and z respectively, $\omega = 7.29 \times 10^{-5}$ sec⁻¹ is the angular velocity of the rotation of the earth, R is the gas constant, p' and T' are the pressure and temperature deviations from their standard values $\widetilde{p}(z)$ and $\widetilde{T}(z)$, $\widetilde{f}(z)$ is the standard density, f(z) is the actual vertical temperature gradient, f(z) is the adiabatic temperature gradient. Assuming that the atmosphere is solenoidal and the movement quasigeostrophic, author obtains the following equation for the function of the flow:

Here $\xi = p(z)/P$, P is the standard pressure at sea level, Δ is the Laplace operator

$$(A,B) = \frac{\partial A}{\partial \theta} \frac{\partial B}{\partial \lambda} - \frac{\partial A}{\partial \lambda} \frac{\partial B}{\partial \lambda}, T = \frac{R^2 T_1}{4a^2 \omega^2 g} \frac{\gamma_a - \gamma_b}{\cos^2 \theta}$$

Abst#3B704 (cont'd)

g is the velocity due to the force of gravity. The task is solved for following limit conditions: 1) $\frac{1}{\sqrt{2}} \frac{1}{\sqrt{2}}$ is limited when $\frac{1}{2} = 0$; 2) $w = \frac{2}{\sqrt{2}} \frac{1}{\sqrt{2}} + \frac{u}{a \sin \sqrt{2}}$ on the surface of the mountain, where $h = h(t^2, \lambda)$ is the equation of the surface of the mountain. Finally

 $h = h(t^0, \lambda)$ is the equation of the surface of the mountain. Finally the solution for $\tilde{c}^0\psi/\tilde{c}^0$ t is thus written

$$\frac{\partial}{\partial t} = \frac{1}{2^{1/2}} \left\{ \int_{0}^{2\pi} \int_{0}^{\pi/2} G_{\xi'=1} \left[\frac{2a^{3} \omega g \cos \theta'}{R T_{1} \xi_{h}} (\psi, h)_{\xi=\xi_{h}} - \frac{1}{R} (\psi, h)_{\xi=\xi_{h}} \right] d\theta' d\lambda' - \int_{0}^{1/2\pi} \int_{0}^{\pi/2} G(\psi, L) d\theta' d\lambda' d\xi' \right\}$$

where

$$G_{\xi'=1} = G(\delta', \lambda', 1, \theta, \lambda, \xi), L = -\frac{1}{\Gamma} \frac{\partial}{\partial \xi} \left(\xi^{2} \frac{\partial \psi}{\partial \zeta} \right) - \Delta \psi - 2a^{2} \omega \cos \theta$$

$$G = \frac{\Gamma}{2 \sqrt{\xi \xi'}} \sum_{n=1}^{\infty} \frac{2n+1}{2N} \left(\frac{2N+1}{2N-1} e^{-N \ln \frac{1}{4k'}} + e^{-N \ln \frac{1}{4k'}} \right) \times \left[P_{n}(\cos \gamma) - P_{n}(\cos \overline{\gamma}) \right]$$

3/4

Abst#32704 (cont'd)

An original method is suggested for the approximation summing up the series representing the functions of the influence. The computed functions of the influence are shown by graphs.

Sh. Mysaelyan

HZh Mekhanika 3-68 Abst#3B736 Mechanics/Hydrorechanics/Hovemonics of Idquid and Cas Mintures

DYUEYUK A. F. HSU Hsiyao-chin

Determination of the Wind over the Mountains in a Pressure Field with Varying Friction Coefficient in a Limited and Unlimited Turbuleut Atmosphere

Izv. AN SSSR Ser, geof. (News of the Academy of Sciences USBR Series Geophysics) 1961, No 7, pp 1078-1084

Investigation of a three-dimensional nonstationary task to dedermine on the basis of movement equations the horizontal velocity components u and v above a mountain for a definite pressure field. Taken into account is the eddy viscosity in vertical as well as in horizontal directions. The coefficients of the eddy viscosity are considered to be definite functions of the coordinates x. y a. i z. The convective derivates of the velocity are assumed to be equal to zero or to be known functions of the coordinates and of time, wherefore a linear task is investigated. The baric gradient is considered

[Abst#3B736 (cont'd)

to be a definite function of the coordinates and of time. One assumes t, and v to be zero on the surface of the mountain z = h(x, y) while the wind is considered to be geotrophic on a certain fixed level z = H. Resides that the distribution of u and v is set for the vertical boundaries $x = t L_1$, $y = t L_2$ and the initial moment t = 0. The solution of the task is obtained through an operative transformation of the variable t with subsequent solution of the equations in the images with Galerkin's method and return to the original ones with the aid of a convolution formula. The solution is expressed by multiple sums of multiple integrals. By the transition to t = 4 a stationary solution is obtained, while by the transition to $L_1 = L_2 = R = \infty$ the solution for the semirestricted domain is obtained. Authors confined themselves to computation leading to the general solution restricted to its boundary forms. Besides that, a sketch of the equivelocity contours is shown having no connection with the text, they are in relation to the profile of a mountain characterized by $h = h_0/(1+cx^5)$. (ha and c are parameters).

L. Gandin

R2h Mekhanika 3-62 Abst#30272 Mechanics/Elasticity and Plasticity/ Ground Mechanics

KUO Ning

Determination of the Resistance of Long Piles

8b.Leningr, in-ta insh.zh-d transp. (Proceedings of the Leningrad Institute of Railway Transport Engineering) 1958, issue 163, pp 99-127

In order to determine the supporting power of long piles an approximation computation formula is established with the aid of the methods of the theories on elasticity and plasticity.

Referent's comment: Berezantsev and Kuo ming have subsequently improved the proposals of computation (Foundations and Fundaments. Scientific-Technologic Bulletin, 1959, No 22).

V. Sipidin

1.1/

TRZh Mekhanika 3-62 Abst#3C294 Mechanics/Missticity and Plasticity/ Ground Mechanics

MIEH An-tin ZASHCHUK I. V.

Measuring of Tensions in Soils with Ultrasonic Waves

Sb. tr. Khar'kovsk, avtomob-dor, in-t (Annual Volume of the Khar'kov Institute of Automobile Roads) 1961, issue 25, pp 97-103

[No abstract]

RZh Mekhanika 3-62 Absv#3C383K Mechanics/Elasticity and Flasticity/Rods and Rod Systems/ Girders

HSU Chih-lun

Theory of Elesticity. Textbook for Advanced Educational Institutions

Shanghai. Jenmin chisouvu ch'upanshe 1960 295 thousand characters; 1 yuan 40

No abstract]

L'//

RZh Mekhanika 4-62 Abst#4B861 Mechanics/Hydromechanics/Movement of Liquids and Gases in Porous Media

LIU Tz'u-ch'iun

Water Afflux in Horizontal Drain Pipes in a Finite Double-Layer Stratum

Izv. AN SSSR Otd tekhn i mekhan i meshinostr, (News of the Division of Technology, Mechanics and Machine Building of the Academy of Sciences USSR) 1961, No 3, pp 193-195

Obtained is the solution of the task bearing on the afflux of groundwater into the horizontal drains in a stratum which is confined on the top by a layer of even potential and below by a waterbearing layer of different water permeability; a horizontal water-repellent layer stretches under the latter. In order to solve the problem the method based on the theorem of the function of a complex variable is used which P. Ya. Polubarinova-Kochina has employed in the investigation of flows caused by point eddies in a multilayer medium (Some Problems of the Plane Movements of Groundwater Publishing House of the AS USSR 1942); by B. K. Rizenkampf (Records of the Saratov University 1940, 15, issue 5); by N. K. Kalinin (Reports of the AS USSR 1941, 30.)

Abst#43861 (cont'd)

No 7). Author follows this method by substituting point drains for the eddies. In that case the complex velocities are thus expressed; in the top layer

$$a_1 - u_1 - iv_2 = \frac{q}{2\pi h_2} \left(\frac{1}{s + il} - \frac{1}{s - il} \right) + \frac{a_0}{\delta} \left[A_1(a) e^{ias} + B_1(a) e^{-ias} \right] da$$

in the bottom layer

$$\omega_{2} = u_{2} - iv_{2} - \int_{0}^{\infty} [A_{2}(a) e^{iax} + B_{2}(a) e^{-iax}] da$$

Here z = x + iy is the complex coordinate of the domain of filtration; q is the intensivity of the flow; il is the ordinate of its location, k_1 is the filtration coefficient of the top layer, $A_1(\mathcal{C})$, $A_2(\mathcal{C})$, $B_1(\mathcal{C})$ and $B_2(\mathcal{C})$ are complex functions of the actual variable \mathcal{C} , determined from the limit conditions. Author obtains after adequate transformations the equation of the complex potential in the top layer

$$W'(z) = h_1 + i\psi_1 = \int \omega_1(z) dz$$

Abst#4B861 (cont'd)

h₁ and q. Corresponding formulae are obtained also for the particular case when the bettem layer has an infinite depth. A layout of this kind has been investigated previously by the author (News of the AS USSR. Division of Technology and Mechanics and Machine Building, 1960, No 3, pp 157-158, RZh Nekh 1961, 8 B 661)

Y. Bochever

3/3

RZh Mekhanika 4-62 Abst#4C376 Mechanics/Elasticity and Plasticity/ Rods and Rod Systems

WANG Ch'1-cho

Computation of Statistically Undetermined Constructions with the Electric Analogy Method

Tumu gong-cheng xuebao (In the Chinese <u>J. Civil Engineering</u>) 1960, No 3, pp 3-19

The methods of electric modelling are investigated for frames with nonmiscible nodes, cover plates, framework of industrial constructions, computing them from the angle of strength and stability. The analysis and the comparison are given for the different scheme-analogies modelling the bars under deflection. The article is of survey character and comprises a considerable amount of references bearing on the electric modelling of systems composed of bars.

K. Kerepyan

RZh Mekhanika 4-62

1

Abst#4C421 Mechanics/Elasticity and Plasticity/ Strength of Constructions

CH'TEN Ling-hei (in the original CH'ENG Ling-hei) T'ANG Heiu-chin T'ANG Chun TS'AO Li-ch'eng (in the original TSAO Li-ch'eng)

Computation of Arched Dams with the "Cantilever Arch" Method Taking Luto Account Torsional Forces

Scientia sinica 1961, 10, No 4, pp 449-482 (Russian) Cf. Delian gongmusyuan xuekan 1959, No 6, pp 11-30

[No abstract]

11/1

25

Abst#5A65 Mechanics/General Mechanics

5-62

LIU Yen-chu

RZh Mekhanika

Dynamics of Damper Gyroscopes

Vestn. Mosk: un-ta Matem. mekhan. (News of Moscow University of Mathematical Mechanics) 1961, No 4, pp 48-57 (English summary)

Equations are established of the movement of gimbal suspension gyroscopes moving according to a definite rule. Following is assumed:

1) the rings of the Cardan joint are connected with the body through spring and oil buffers; 2) the axes of rotation of the external and internal rings are neither the central nor the main axes; 3) the axes of the rotor and the two rings are not perpendicular to each other nor do they intersect; 4) thenter of mass of the rotor is located on the axis of rotation. In case of several special laws of the movement of the basis, the simplification of the obtained equations is carried through and conclusions on quality are drawn.

1/1

V. Krementulo

RZh Mekhanika 5-62 Abst#5Al24 Mechanics/General Mechanics

CHANG Sau-ying

A Theorem of Optimum Control

Prikl: matem: 1 mekhan (Applied Mathematics and Mechanics) 1961, 25, pp 413-419

The task is thus set: to find through Lagrangian common multiples the increase of the optimizing functional

$$S = \sum_{i=1}^{n} c_i x_i \ (T) \tag{1}$$

in the task on the optimum control of a system expressed by the equation

$$\dot{x}_l = f_l(x_1, ..., x_n; u_1, ..., u_r) \ (l = 1, ..., n)$$

where x_1 are the phase coordinates of the system. u_1, \ldots, u_r are the locations of the control operators. Author denominates "Permissible controls" cyclically continuous time functions $u_1(t)$, $u_r(t)$ sat-

TAbst#5Al24 (cont'd)

isrying the condition at any time

(425 and 44) # 0 (f = 1, ..., 11) ...

However the set task is actually solved for a case, when no restrictions are imposed on $u_1(i-1,\ldots,r)$, as the author in page 415 of the work considers the variations $0u_1,\ldots,0u_r$ independent. Besides that, what is of great importance, the character of these variations is not specified. A formula bearing on the increase of the functional (1) is established in the article, further also equations which have to be satisfied by the optimum trajectory. It is demonstrated that in the task of optimum control (when $i=1,\ldots,r$ stands good for $u_1(t)$) limitation (3) is not applied and it can be solved with the classical variation calculus. This result is well known (Fontrysgin L. S. Achievements of the Mathematical Sciences. 1959, 14, No 1).

I. Litovchenko

(3)

1_2/2

RZh Mekbanika 5-62 Abst#5B153 Mechanics/Hydromechanics/ Dynamics of Gases and Aerodynamics

WANG Shih-ts'um

Generalization of the Eddy Theory of the Lifting Propeller

Tr. Mosk sviats in-ts (Transactions of the Moscow Aircraft Institute) 1961, issue 142, pp 25-80

Formulae are presented for the computation of the three components of the mean inductive velocity at an arbitrary point of the space. An arbitrary angle of incidence is investigated; changes in circulation in relation to the azimuth are examined. Formulae of a form suitable for numerical integration are presented. For particular cases are obtained formulae presented previously in works of other authors.

G. Maykapar

1 1/1

RZh Mekhanika 5-62 MITKALINNYY V. I. HE Yu-chin Abst#58249 Mechanics/Hydromechanics/Dynamics of Gases and Aerodynamics

Some Aerodynamic Problems on Martin Furnaces of a Capacity of 600-900 t According to the Data of Investigations on Models

Sb. nauch.tr. Zhdanovsk metallurg.in-t (Collection of the Scientific Transactions of the Zhdanov Metallurgic Institute) 1961, issue 7, pp 218-230

The methods and results obtained by experimental investigations are described; they were carried out with burners installed at different angles on an aerodynamic model of the operative area of a Martin furnace. The model was made of organic glass at a scale of 1:50. The picture of the movement of the water in the operative area could be studied visually on the hydraulic model while the distribution of the pressures and the velocities in the different sections of the operative area could be studied on the air model.

Different air input schemes were studied, further several modifications of the cap of the Martin furnace. The picture of the flow

Abst#5B249 (cont'd)

in the model furnace was determined permitting suggestions regarding the rational shapes of furnaces.

Yu.Dityakin

Abat#58771 Mechanics/Hydromechanics/Movement of Liquid and Gas Mixtures

SMOLDYKEV A. E. HUANG Chiang-teeng KORSHUNOV A. P.

Problems of Mydraulic Conveying of Coal and Rocks

Tr.1-cv Vess.rauchn-tekhn, konferentsii po gidravl. dobyche uglya (Transactions of the All-Union Scientifico-Technologic/Conference on Hydraulic Production of Coel) Moscow, 1959, pp 592-596

The movement of lumps of coal or rocks of different shape in tubings is investigated. The starting velocity of the grains of the conveyed material and its relative movement velocity compared to the vater flow were investigated in ratio of the grain size and tube diameter. The tests were carried out withscine-speedometer. The characteristics of suction dredges were established at a suction height of 1.5 m and at a suction line length of 15 m. The suction dredge was operated with circulating hydraulic mixture. Examinations of such kind were carried out with sand, gravel, and gravel-sand mixture.

D. Roshchupkin

RZh Mekhanika 5-62 Abst#5B845 Mechanics/Movement of Liquids and Gases in Porous Media

LIU Tr'u-ch' jung

The Africa of the Fluid in a Circular Field of Wells with Uniform Yield in a Circular Reterogeneous Layer

Izv. AN SSSR Otd. tekhp i mekhan, i mashipostr. (News of the Academy of Sciences UESR, Division of Technology and Mechanics and Machine Building) 1961, No 5, pp 168-170

Expressions of the velocity potentials and of the yields of wells are presented by the methods of the theorems of functions of complex variables; these are wells located in a layer composed of two concentrical zones of different permeability.

G. Tsybul'skiy

Abst#50236 Mechanics/Elasticity and Plasticity

CH'EN Chen-cheng

Collision of Elastico-Plastic Bars of Different Length

Isy AN SSSR otd.tekhn.i mekh.i mashinstr. (News of the Academy of Sciences USSR, Division of Technology, Mechanics and Machine Building) 1961. No 1, pp 39-45

The longitudinal collision of elastice-plastic bars of different length and identical section is investigated. Given is a diagram for the material of the bars having a linear sector; the lengthwise distribution of the tensions, deformations and velocities in case of considerable plastic deformations are determined by the distribution curve for the time of the clash and also the time when the contact of the bars has ceased. A clash of such velocity is investigated, which causes plastic waves of strong discontinuity, but it is assumed that after repulsion from the free ends in case of an interaction with the Riemann waves the tension waves do not cease to be relieving waves

TAbst#50236 (cont'd)

and that after the passing of the relieving wave the tensions in the bar do not exceed new elastic limits. Four references.

B. Malyshev

1 2/2

Abst#50402 Mechanics/Elasticity and Plasticity

LIU Huei-haiach

Computation of Seismic Loading of Civil and Industrial Buildings Jianshu xuebao 1961, No 8, pp 20-26

[No abstract]

TiiZh Mekhanika

1//

5-62

Abst#5040 Mechanics/Elasticity and Flasticity

MANG Chin-po

The Influence of the Modulus of Elasticity of the Railway Bed on the Tensions Arising on the Surface of the Webs of Rail.

Sb. Materialov VII Nauchno-tekhn-konferentsii po vopros putebogo kh-va (Subjects of the 7-th Scientifico-TechnologicalConference on Questions of Traffic) Leningrad, 1961, pp 32-35

[No abstract]

L1/1

Abst#5C423 Mechanics/Elasticity and Plasticity

CHAO Tau-su

Limit Equilibrium of Reinforced Concrete Plates

Tr. Tsentr. n-i in-ta stroit, konstruktsiy Akad. Stroit-va i arkhitekt. SSSR (Transactions of the Central Institute of Building Constructions, Academy of Construction and Architecture, USSR) 1961, issue 4, pp 226-236

Based on the yielding point of the reinforced concrete plate expressed by $M_1 = \frac{1}{2} m_{\rm P}$, $M_2 = \frac{1}{2} m_{\rm H}$ (where M_1 , M_2 are the main moments) and making use of the results obtained by Halasz (Isv AN SSSR Section of Technological Sciences 1956, No 8, pp 42-54 - RZh Mekhanika, 1957, No 10, 12131) author determines by the energy method the loading capacity of hinged independent plates loaded with uniform pressure, under the condition that the plate when destructed gives rise to a convex surface. Formulae and numerical results are presented for elliptical, square and rectangular plates. The case is also investigated bearing on the

TAbet#50423 (cont'd)

load by a concentrated force; the results obtained for that are tallying with the determinations of AR Rahanitsin (Computation of reinforcements taking into consideration the plastic properties of the materials. State Publishing House for Construction and Architecture. - 1954, 288 pages. - RZh Mekh. 1957, No 8, 9428 K.)

V. Rosenblyum

Abst#50426 Mechanics/Elasticity and Plasticity

TS'AI Shao-huai

Computation of the Stability of Circular Reinforced Concrete Plates by the Limit Equilibrium Method. 1, 2.

Jianzhu xuebao 1961, No 9, pp 21-24; No 10, pp 28-31, No 11, pp 30-33

[No abstract]

RZh Mekhanika 5-62

Abst50456 Mechanics/Rlasticity and Plasticity

CH'E Shib-ywan

Advice for Determining the Cracking Stability of Prestressed Elements Yignshu xuebeo 1961, No 10, pp 32-31 [sie].

[No abstract]

RZh Mokhenika 6-60 Abst#6A150 Mechanics/ General Mechanics
Therefore of Mechanisms and Machines

CHIMNS To mehation

Kinematic Analysis of Fourlinked Mechanisms with SphericalPairs by the Matrix Method

Ist, vyesh, nehebn savedeniy. Mashinestremeniye. (New of the Schools Righer Muration. Machine Building) 1981, 30 1, pp 39-53

The tasks of determining the positions of spatial fourlinked mechanisms are solved by matrices of transform of the Cartesian co-ordinates. Advices are given how to chose the system of coordinates connected with the semarate links.

S. G. Kielitsyn

1/1

NZh Nekhanika

Abst#68153 Nochanics/Hydromechanics/Dynamics of Gases and Aerodynamics

WANG Shi-ts'um

Aerodynamic Characteristics of the Lifting Propeller of the Heliospter Taking into Account the Circulation Change Due to the Azimuth

Izv, vyssh.uchebn, savedeniv. Aviate tekhn (News of the School of Nigher Education. Aircraft Technology) 1961, No 2, pp 26-34

Formulae are presented for the computation of the traction and efficiency coefficients. The circulation is approximately given by a series

#F.4 -# 77 (1 + AF one + + #F de + ...)

The mean circulation in reference to the azimuth is $H(r) = Ax^{2k}(1-r^{2k})$

An enample of the computation is given; its results are compared with the computed figures for a propellar of the same kind without taking into account the change of communication due to the assumbt.

1/1

T. B. Materekiy

Abst#6B670 Mechanics/Hydromechanics/Dynamic Meteorology

DYUBYUK A. F. HSU Hauso-chin

The Ritz-Galerkin Method for Solving the Task of an Air Flow Around a Mountain at a Definite Pressure Field in the Turbulent Atmosphere

Vestp. Nosk.up-ta Fig. astrop. (News of the Moscow University. Physics. Astronomy) 1961, No 4, pp 59-67

The problem is investigated on an air flowing around a mountain of the arbitrary definite profile z=h(x,y). Account is taken of the unsteadiness, the eddy viscosity, the Coriolis force and the force of the baric gradient which is conjectured to be a definite function of the coordinates and of time. The coefficients of the eddy viscosity v_1 in the vertical and v_2 in the horizontal sense are considered to be definite constants. A linear task is investigated disregarding the convective derivative velocity. It is demonstrated that one can solve the nonlinear tasks with subsequent approximations, substituting in order to determine the following approximation the convective de-

TADat#6B670 (cont'd)

rivatives computed for each preceding approximation in the right part of the equations.

Operative transformation by the time t is used for the solution of the task. The equations for transformation are solved by the Ritz-Galerkin approximation method. The products of trigonometric functions are used as basic functions, they return to zero on the level h, on the upper boundary of the area perturbated by the mountain z=H and on the vertical boundaries of this area $x=L_1$ and $y=L_2$. The values H, L_1 and L_2 are considered as given constants. Detailed computations are presented in the article, further the general solution of the task is deduced. The stationary solution obtained from the general solution by the limit transition at $t \rightarrow \infty$ is likewise deructed.

Actual computations are shown for a two-dimensional task with the additional assumptions, that the components of the baric gradient are constant, $v_1 = v_2$ and $h = h(x) = a/(1+c^2x^2)$, where a and c are parameters whose conjectured values are not shown. The results of the computations are submitted to a qualitative analysis. Graphs are shown representing the equal-velocity lines above the spuntain.

Abst#6B670 (cont'd)

The article contains misprints. Seven references.

L. S. Gandin

1 3/3

RZh Mekhanika 6-62

Abst#60446 Mechanics/Elasticity and Plasticity

CHANG Che-wen

Bending Oscillations of a Revolving Rotor on an Elastic-Damping Support

Tr. Mosk, aviats, in-ta (Transactions of the Moscow Aviation Institute) 1961, issue 136, pp 57-92

The amplitudes of constrained bending oscillations of a rotary shaft on two supports are determined by taking into account the yielding of the support and the hydroscopic moments of the disks in the presence of an active damper with viscous friction. A system of two integral equations is established referring to the projections of the rotary shaft on the mobile coordinates. The solution of the integral equation system is carried out by iteration. The shown numeric examples of determination of the amplitude of the constraint oscillations in the subresonance and resonance operative ranges verify that the iteration process coincides soon enough: already the second approximation gives satisfying accuracy. 111

B. M. Vysochin

2539

CSO 3550-N

7-62 Mekhanika

Abst#7A50 Fechanics/General Mechanics

SHIH Yen-fo

On the Number of Noncalibrated Complexes and Simplexes Obtained by the Dimension Analysis Method

Inzh-fiz sh (Engineer Physicist Journal) 1961. 4, No 12, pp 102-105 (English summary)

[No abstract]

1/1

RZh Mekhanika 7-62

Abst#7B356 Mechanics/Elasticity and Plasticity

CH'IEN I-liang

Static Computation of a Cable Suspension Roof Strengthened with Double Cables by Taking into Account Prestress

Jianzhu xuebao 1961, No 9, pp 25-31

[No abstract]

Abst#7B390 Mechanics/Hydrodynamics and Hydraulics

RZh Mekhanika 7-62

CH'EN Huei-ch'uan

Pressure Distribution in the Outlet Part of a Water Conduit

Scientia Sinica 1961, 10, No 2. pp 237-266

The research was devoted to the investigation of the pressure distribution in the outlet part of a waterconduit of constant cross section at free discharge of the fluid. The author understands under outlet part the extreme sector of the conduit on which the pressure distribution is different from the hydrostatic pressure. The experimental tests were carried out on conduits of 7.5 to 15 cm diameter with different roughness of the walls. The pressure distribution in the cross section of the outlet and along the end sector; the influence of warming up and of the boundary conditions in the outlet (the duct's cross section below the outlet, the angle of widening the side walls, the gradient of the bottom etc.) were investigated in detail on the piezometric line. The theoretical examination of the problem was carried out for a circular pipe at free discharge of the flow. The pressure

Abst#7B390 (cont'd)

distribution in the cross section of the pipe was searched for by the aid of Euler's equation, the continuity and the experimental function establishing the relation of the variance of the pressure and of the hydrostatic pressure to the kinetic compression in the point. Making use of the force function and several empirical relations author locates the position of the piezometric line along the outlet part for the top and bottom points of the pipe. The computation and the test tally well. Advices are given for the reduction of the negative pressures in the upper part of the water pipe. G. P. Skrebkov

Abst#78716 Mechanics/Dynamic Meteorology

YEH Tu-cheng

YEH Tu-cheng CHU Pas-chen

Several Questions of Great Importance on the General Circulation of the Atmosphere

Translated from Chinese, Leningrad, Gidrometeoizdat 1961, pp 240, 111 maps 1 ruble 30 kopecks.

No abstract

12/1

Rib Mekbanika 7-62 Nost#70231 Mechanics/Elasticity and Plasticity

TSENG Sheng-k'uei CHU Ch'ien-fang

Comparison of Some Formulae on the Computation of the Supporting Power of a Single File

Jianghu xuebac 1961, No 2. pp 31-33, 30.

No abstract]

Abst#78242 Mechanics/Hydromechanics

STECHMEN B. S. DUBENSKIY M. G. SOKOLOV K. K. TS'AC Heiso-ching

On the Radial Equilibrium of the Flow

Izv AN SSSR Otd tekhn p (News of the Academy of Technical Sciences USSR. Department of Technical Sciences) 1961, No 4, pp 11-15

Authors wrote the essay to refute the well known conclusion of the theorem of the axial turbines which denies the possibility of investigating the axially symmetrical eddy flow behind the guide vanes. The results shown imply the measurements of the flow angles on the discharge edges of the twisted blades in the straight guide vanes. G. Yu. Stepanov

1/1

RZh Mekhanika

Abst#70512 Mechanics/Strength of Materials

LI Kuang-tsung

Experimental Investigation of the Creep of Old Age Concrete

Izv Vses n-i in-ta gidrotekhn (News of the All-Union Scientific Institute of Hydrotechnology) 1960, 66, pp 211-226

The results of the experimental check-up on some physical prerequisites of the creep theorem of concrete are shown. The investigations were carried out on air stored concrete test pieces of 5x5x20 cm.
The specimens were tested for axial compression with varying loads,
(the atress changed stepwise from 0 = 0.14 - 0.23 R_{lim} to 0 =
= 0.70 - 0.90 R_{lim}, the working duration of each step of stress was
one hour, one d and seven days), for axial compression with continuous constant load and with lasting deformation i. e., for relaxation.
The principle of the application of the creep deformation is fulfilled with stepwise load. The linear function between the creep deformations and the stresses is valid up to a certain value of the stress

Abst#70512 (cont'd)

which increases with the rise of the load duration. The curves of the creep deformations for different stresses are alike in case of stresses not exceeding 0.8 to 0.85 $R_{\rm lim}$. The curves of the creep deformations are alike at different loading durations up to dying out more exactly in the initial period after the application of the load. S. Z. Vul'fson

5/2

2539 |CSO 3550-N Rith Mekhanika

Abst#9A136 Mechanics/General Mechanics

CHANG Jen-wei

Setup of Relay Systems by the Minimum of Integral Square Deviations

Automatika i telemekhanika (Automation and Telemechanics) 1961. 22, No. 12, pp. 1601-1607 (English summary)

A Lyapunov function is set up for a control system expressed by the differential function

 $\dot{x} = Ax \ . \tag{1}$

where A is a constant matrix. Its derivative is in compliance with (1) to the set square form

$$v = -\sum_{i=1}^{n} a_i x_i^2$$

Further, author investigates the system

(2)

1/2

x -- Ax + au

Abst#9A136 (cont.td)

where c is a vector, u is a scalar function which fits u thus, that the decreasing velocity of the function w be at the maximum in every given moment. Later on author affirms that the equation he has found secures along the trajectory the minimum of the integral

Reviewer's comment: The above-said affirmation of the author is erroneous. In the course of demonstration the author makes use of the solution of the system (19); this system is however incompatible with n > 1. - Ye. A. Barbachia.

Rith Mexhanika

Abst#9A1882 Mechanics/General Mechanics

K'AR Tou-wing

Dynamic Investigation of an Electrically Operated Power System

Arthorf disa kand tekhn In-t reshipoved gos kom-ta (Author's Abstract of his Cardidate of Technical Sciences Dissertation. Institute of the Science of Machines of the State Committee of the Soviet Ministry USSR for Automation and Mechanization) Moscow, 1962

No abstract

1/1

RZh Mekhanika 9-62 Abst#98756 Mechanics/Movements of Liquids and disea in Porous Media

II i -ebang Sechiolbakov G. V.

On the Determination of a Layer's Parameters by a Testing Sampler Relying on the Data of Investigation of the Well's Inflow

<u>Manches-takin ab po dobyche nefti</u> (Collection of Scientific Technological Papers on Odl Production) All-Union Scientific Petrolema-Gas Institute 1961, No 15, pp 77-79

As far as the discharge of a certain quantity of fluid in the testing apparatus occurs after a short lapse of time the authors intend to make use of the pressure changes in the layer which arises with this process to determine an instantaneous spring. Working up the checked pressures in coordinates $\ln(t\Delta p)$ and 1/t the basic hydrodynamic parameters of the layer can be established. A numeric example is quoted showing that the devices may fix the arising depressions. There are misprints in the article. G. P. Taybul'skiy

Abst#90152 Mechanics/Elasticity and Plasticity

CH'ENG Ch'ing-tung CHUNG Cho-jan

Vibrations of Slanting Shells under the Effect of Dynamic Load

Janshu xuebeo 1961, No 2, pp. 27-30.

[No abstract]

17/1

RZh Mekbanika 9-62

Abst#90188 Mechanics/Plasticity Creep, Soil Mechanics

LIU Ch'uan-sheng

A Method of Computing the Effect of Earthquakes on Manystoried Frame-work Buildings

Jianzhu xuebao 1961, No 3, pp 35-37

Author preposes the basis for the method of appraisal of the seismic spectrum suggested by S. V. Medvedev (Establishing of Earthquakes. Bulletin of the Council for Seismology of the Academy of Sciences USER, 1957, 6) taking into account the standards of occuputation of structures in seismic regions (SN-8-57). Author quotes this reference back and proposes the modification of the method of occuputing only in the part where this method needs the determination of the basic period of vibration of the structure. By that -- as it is usual in the literature dealing with the investigation of the seismic activity on structures -- a composite elastic model of the structures (masses with elastic joints) has been used. The searching 1/2

Abst#90188 (cont'd)

of the first frequencies (periods) of the vibrations is a wieldy task for the sufficiently intricate systems of the author with examples of four-, fivestoried buildings (i. e., one section comprises to 5 centers of mass). Author proposes to employ in this case S. A. Lerishteyn's bilateral appraisal for the radicals of the characteristic determinant. Two numerical examples are investigated. Ye. I. Shenyakin

5/5

RZh Mekhanika 9-62 Abst#9C262 Mechanics/Plasticity, Creep, Soil Mechanics

TING Chun-bsi

Graphic Computation of the Maximum Thrust and Plane of the Caving in of the Soil for Bulkheads

Jianahu xuebao 1961, No 2, 38

[No abstract]

Abst#10A143 Mechanics/Theory of Mechanisms and Machines

CHANG Iz'u-hsien

Kinematic Analysis of Devices with Lowest Pairs by the Matrix Method

Izv vyssh uchebn zavedeniy. Mashinostroyeniye (News of Higher Educational Institutions. Machine Building) 1961, No 2, pp 14-30

The synoptic survey of a certain method of determining the disposition of devices by transformation to cartesian coordinates with the aid of matrices is here given. Recommendations on the advisable choice of the coordinate systems connected with the separate links of the device are quoted. The problem of the determination of the dispositions and angular velocities of four-link spatial devices without ball and socket joints is investigated. The general considerations are elucidated by examples of Bennet-Verkhovskiy devices, a spherical device with rotary pairs and a plane hinged four-link joint. S. G. Kislitsyn

1/1

RZh Mekhanika

Abst#10B594 Mechanics/Hydromechanics

YANG Wen-chich

Dynamic Characteristics and Resonance of Heat Exchangers of One Material and Operating on One Fluid I. Zero Relative Heat Capacity of the Walls

Nikhon kikay zakkay rombunsyu. Trans Japan Soc Mech Engrs 1961, 27. No 180. 1276-1283, Discuss 1284-1285 (Japanese, English summary)

Theoretical investigation of the dynamic claracteristics of the fluid and the temperature of the walls of the heat exchanger consisting of one material and operating on one fluid at zero relative heat capacity between the fluid and the walls. The issues of the investigations demonstrate that the distribution of the periodical thermal load produces resonance oscillations of the relative value and phase displacement of the temperatures of the fluid and the walls. These resonance phenomena are explained by the changes of the enthalpy of the particles of the fluid flowing through the heat exchanger. Summary.

RZh Nekhanika

Abst#108683 Mechanics/Rydremachanics

GUSEV V. D.

Dependence of the Measured Parameters of a Seterogeneous Ionosphere on its Perturbation

Yestm Mock un-to fix actr (Hereld of the Meaner University Physician) Astronomy 1982, No 2, up 46-50

[No abstract]

1/1

RZh Mekhanika 10-62

Abst#108603 Mechanics/Hydromechanics

LANG Chang-heing

Nethod to Compute the Gas Inflow in a Range of Wells

Inv vyseh uchebn savedeniv Neft' i mas (News of Higher Educational Institutions Petaleus and Gas) 1962, No 2, pp 53-58

The approximation solution is given bearing on the task of the first phase of the gas inflow in a range of wells of constant yield in a closed circular layer homogeneous with regard to all parameters. By introducing in the examination the weighted mean pressure on the line along which the wells are located, author substituted the actual flow with a symmetrical radial one. Fellowing expression has been used for the pressure function

where the coefficients L(t), N(t) and N(t) are determined by the border L/2

Abst#10B803 (cont'd)

conditions, and the radius of the influence l(t) by integral relations analogous to those employed previously by A. M. Priverdyan and E. S. Babich (Translations of the Azerbaydzhan Sc.Res.Inst. for Petrol. production 1953, No 7) G. P. Tsybul'skiy

5/5

RZh Mekhanika

Abst#10B804 Mechanics/Hydromechanics

IANG Chang-heing

Computation of the Exhaustion of a Gas Layer Drained by a Range of Wells

Izv vyssh uchebn zavedeniy. Neft' i gas (News of Higher Educational Institutions. Petroleus and Gas) 1962, No 3, pp 43-48

The approximation computation method is given for the second phase of the gas inflow in a range of wells of constant yield in a closed circular layer of uniform thickness and permeability. As in the preceding article dealing with the investigation of the first phase (cf ref 108803) author uses here too the concept of the weighted mean pressure on the line along which the wells are located and substitutes an axially symmetric flow for the actual flow. The expressions for the external and internal pressure functions in the areas in relation to the diagram of the range of wells are taken from the same article. The pressure values in the center and on the border of the layer entering in these formulae are determined by certain integral relations. G. P. Tsybul'skiy

Abst#11A131 Mechanics/General Mechanics

CHANG Jen-wei

Synthesis of an Optimum Controller in Systems with Retardation

Avtomatika i telemekhanika (Automation and Telemechanics) 1962, 23, No 2, pp 133-137 (English summary)

Under investigation is a control system whose perturbated motion is expressed by a system of equations with retardation argument

$$\dot{z}_{i}(t) = \sum_{j=1}^{n} a_{ij} x_{j}(t) + \sum_{j=1}^{n} b_{ij} x_{j}(t-e) + b_{i} u$$

$$(i-1,2,\ldots,n), \ z_{i}(t) = q_{i}(t), \quad -e < t < 0$$
(1)

where aij. bij, bi and T are constants, 7>0

One has to find among the permissible equations $u(x_1, \dots, x_n)$ securing the asymptotic stability of the solutions of the system (1), the minimizing functional 1/2

Abst#11A131 (cont'd)

$$J = \int_{0}^{\infty} \left[\sum_{l=1}^{n} a_{l} \pi_{l}^{2} (l) + cu^{n} (l) \right] dt$$

In the assumption that Z is small, the graphs of the initial functions $\mathcal{G}_1(t)$ (i = 1, 2, ..., n), and $Z \le t \le 0$ determining the solution of system (1) are substituted by direct ones; it is sufficient for their solution to supply at two points the values x_1 for example $x_1(0)$ and $x_1(-)$.

Meanwhile the functional J remains with fixed u a function of the arguments $x_1(0)$ and $x_1(-T)$, one can use for the solution of the set task the well known method of dynamic programming. The use of this idea is illustrated with an example of a certain equation of the first degree. ___ L. E. El'sgol'ts

Abst#11B28 Mechanics/Magnetohydraulics

BECK I. V. TAU Yi-toong

Effects with a Laminar Flame Expansion

Vepr. raketn. tekhn. (Problems of the Rocket Technology) Sb. perev. u obs. in. period. lit. 1962, No 6, pp 13-16. Translated J Aero/Space Sci 1961, 28, No 11, pp 908-909
Also see RZh Mekhanika 1962, 6818

[No abstract]

11/1

Rih Mekhanika 11-62 Abst#11B103K Mechanics/Gas Dynamics and Aerodynamics

PAI Shih-i

Introduction into the Theory of Compressible Liquids

Translated from English Moscow. Publishing House for Foreign Literature 1961 (1962), pp 410, ill. 1 ruble 83 kopecks.

[No abstract]

1:/1

Abst#11B562 Mechanies/Hydromechanics

إسر

SHIR Yen-fu ROMANKOV P. G. RASHKOVSKAYA N. P.

Investigations of the Drying Process in a Boiling Loyer

Zh. Prikl. khimii (Journal of Applied Chemistry) 1962, 35, No 3, pp 530-536

Authors obtain, by analyzing the equations of heat exchange and hydrodynamics, the parameters of similarity of the drying process in a boiling layer for periods of constant and decreasing velocity. The tests were carried out in periodically working drying kilns of 100, 150 and 200 mm diameters with activated silica gel, alumosilica gelocal, further with calcined clay. Based on the tests noncalibrated equations were obtained for the heat emission coefficient in the fifth period of drying, for the drying time in the second period, and elso a single noncalibrated equation for the determination of the aggregation.

Abst#11B562 (cont'd)

drying time in a boiling layer.

The comparison of the heat emission coefficients obtained by the authors in the first period with the data of other researchers agrees in a satisfactory way when processed according to the equation

$$N = 0.25R\left(\frac{d}{h}\right)$$

where N and R are the Nusselt's and Reynold's numbers, h is the thickness of the layer, and d is the diameter of the grains. A. P. Baske key

R21. Mektuanika 11-60 Abst#LiB573 Mechanics/Hydron metanics

MANG Fen-chieh

The Distribution of Terperature in a Reat Exchanger with Plastic Ribs

Nixon kikay gakkay pombunsyu. Trans. Japan. Soc. Mech. Engrs 1961. No 177, pp 730-734 Discuss 734-735 (Japan, English summery)

The method is quoted for determining the temperature of liquid and metal in a heat exchanger with plastic ribs. The method has a remeral character and might be applied to any configurations operating with any fluid passing around. The method is illustrated with its use in a recovery unit with transverse flow and in a Z-shaped recovery unit for small desturbines. The conclusion is drawn that the Z-shaped type is more massive and suffers the least from thermal stresses.

1/1

1....

į

TRZh Mekhanika 11-62 Abst#112592 Mechanics/Hydromechanics

KUANG Wel-yen

Investigation of the Jump of Temperature on the Boundary between the Solid Body and the Eslium Flowing Over it

Zh. eksperim. i teor. fiz. (Journal of Experimental and Theoretical Physics) 1962, 42, No 4, pp 921-935 (English summary)

[No abstract]

Abst#115770 Mechanics/Hydromechanics

LANG Chang-hain

Approximation Solution of the Task of the Nonstationary Leakage of the Cas towards the Range of Wells in a Circular Layer of Varying Thickness

Izv. wrash. usbebn. savedeniv Neft' i gaz. (News of the Higher Educational Institutions. Petroleum and Gas) 1962, No 5, pp 63-68

The problem of the movement of the gas in a closed dome shaped layer of a radius R to the sole and a maximum height h in the center n wells with uniform frontal pressure p_c, are located at a distance R₁ from the center. The law is determined bearing on the change of the integral yield G, the pressures on the boundary and in the center of the layer as function of time. The problem is reduced to the solution of a monlinear equation of the heat conductivity, meanwhile the second phase of the continual gas filtration is investigated. By assuming that the exploited range of wells divides the layer in 1/2

Abet#11B770 (cont'd)

two parts, author searches the solution in both parts by the steps r in the form of polynominals, which have coefficients depending on time; that is in accordance with the method of the moment integral relations proposed by G. I. Barenblatt. The obtained differential equations effer the facility to determine numerically the searched values. An example is quoted for a computation with concrete initial figures. — N. V. Filinov

Abst#11087 Mechanics/Elasticity Theory

TUNG Shih-ling

Computation and Application of Some Types of Slantin: Shells

<u>Jianzhu xuebao</u> 1961. No 5, pp 22-26 32; No 6, pp 20-22

[No abstract]

1/1

RZh Mekhanika 11-62 Abst#11093 Mechanics/Elasticity and Plasticity

HSU Yung-chi LIU Chia-jung

Workable Method to Compute New Type of Shell Constructions 4.5.6 Part

Jianzhu xuebao 1961. No 1. pp 27-31; No 2. pp 34-37; No 3. pp 28-34 33

No abstract!

Abst#110322 Nechanics/Plasticity, Creep, Soil Mechanics

WANG Ching-fei MOTOV A. I.

Experimental Investigation of the Supporting Power of Piles Loaded by Scouring

Tr. Lemingro in-to. voin transport (Transactions of the Lemingrad Institute for Water Transport) 1962, No 27, pp 17-23

[No abstract]

1/1

RZh Mekhanika

Abst#11C450 Nechanics/Stability of Constructions

YU Tosi-wa

Static Computation for Symmetric Load of a Circular Suspension Covering with Double Cables

Jianzhu xuebao 1961, No 4, pp 27-30, 20

[No abstract]

Rich Mekhamika

Abst#128428 Mechanics/Hydromechanics/ Boundary Layer

LILU Shen-ts'uan

Computation of the Laminar Boundary Layer in a Moncompressible Liquid in the Presence of Suction and Indraft

Th. vychisl. matem. i matem. fiz. (Journal of Calculation, Mathematics and Mathematical Physics) 1962, 2, No 4, pp 666-683

The first part is consecrated to the computation of the laminar boundary layer in a noncompressible liquid in the presence of suction and indraft by the generalized method of integral functions. The idea of this method lies in the following: The differential equation of the movement's quantity for the boundary layer increases to an arbitrary function f(u) (the function f(u) after having been twice differentiated is rapidly enough striving to zero, when the velocity u approaches the velocity u so on the limit of the boundary layer) and the equation of continuity increases to the function f'(u). Afterwards both equations are summed up and the result obtained is integrated across the $\frac{1}{3}$

Abst#123428 (cont'd)

boundary layer, and one obtains as result an integral equation. The functions searched for in this equation f and f (with accuracy up to the constant common multiple f = $[24/2y]^{-1}$) are approximated through the values of these functions by interpolated polynomials of N-lth degree at some N intermediate points. After having substituted in the integral equation these polynomials, for the function f(u) the functions of the form $f(u) = (1 - u)^n$, where n = 1, 2, ..., N, -- in order to determine N values of the function f in the intermediate points author obtained N regular differential equations. The article quotes expressions for the interpolated polynomials and the differential equations up to the fourth approximation. The computation of a boundary layer is shown for the case, when

How me sh of sach of .

The computed results are presented by tables and graphs.

The second part of the work is consecrated to the solution of the same task but without indraft and suction. Formulae are quoted $\lfloor 2/3 \rfloor$

Abst#12B428 (cont'd)

in order to compute the boundary layer with the method of finite differences. So far as this method is not suitable in the vicinity of the basis of the boundary layer, an approximation solution has been found for this area by the method of series development. It became obvious that the results of the difference computation method tallied very well with the results obtained by the integral relation method. V. M. Kuptsov

13/3

RZh Mekhanika 12-62

Abst#12B608 Mechanics/Hydromechanics

CHOU Hsiao-p'ing

The Problem of the Formation of Cumuli

Izv. AN SSSR Ser. geofiz. (News of the Academy of Sciences USSR. Series of Geophysics) 1962, No 4. pp 548-557

The issue is studied of the initial stage of the development of an axially symmetrical cloud. which arises in the process of solving the atmosphere's wet instability. Three equations of the movement serve as initial equations, - the equation along the vertical is valid in its full form, as the local cloud formation is substantially connected with the instability of the movement; the equation of the heat inflow and the equation of the continuity. The "adhesion" to the earth and the fading of the process by altitude are considered to be the boundary conditions. In the initial moment no movement is present, the temperature deviation from the static distribution $\Phi(x, y, z)$ is considered as given. The coefficients of the turbu-

Abst#128608 (cont'd)

lence friction and temperature mixings are considered constant and uniform (50 m2/uec). The derivatives by t are substituted by differences, the steps in time ere considered to be 20 sec. One obtains equations of the form $(A - a^2)n^2 = f$, for the three velocities and a^2 and Poisson's equation for # (deviation of the pressure from the static pressure reduced to the standard pressure at sea level). The right side contains nonlinear terms and the initial fields, bereto transposed all the functions with the exception of the basic one, i. e., the function standing in the given equation under the symbol of Helmholtz's operator. The derivatives in f are also computed with the difference method, the step $\delta z = \delta r = 100$ m. Green's functions ere calculated previously, so that the task comes to the solution of s system of algebraic equations, while the integration by 0 & 2 & 2 km, 0 < x < 2 km is substituted for the squaring of the half-space. The solution is carried out by the iteration method; one takes as first approximation the value of the function at the end of the previous step. A concrete example has been computed by the Computer BESM-2, in which the function of was thus given, that the atmosphere is unstable in the layer 450 M < z < 650 m. Graphs are quoted for the 2/3

Abst#128608 (cont'd)

velocity distribution and of in time. The results are discussed and it is especially pointed out that after a single wave of the vertical velocity and of have passed the movement trends to settle at the given point. V. M. Kriyshnikov

Abst#12089 Mechanics/Elasticity Theory

VUAN Hsiao-ch'u CH'EN Pao-yuan LIU K'ai-kuo CHUNG Mu-t'ang

Some Theories for Computing Nonreinforced Slanting Shells with Rectangular Base

Jianzhu xuebao 1962, No 1, pp 18-25

[No abstract]

1/1

RZh Mekhanika 12-62

Abst#120102 Mechanics/Elasticity Theory

CHANG Wei-yu CHEN Chao-ting CHEN Chia-feng

Quick Method for Computing Front Arches at Slanting Twofold Curvature Shells

Jianzhu xuebao 1961, No 12, pr 15-23

[No abstract]

Abst#120254 Mechanics/Elasticity and Plasticity

TZ'U Shio-p'ing

Creep of a Boam of Great Curvature at Plane Bend

V sb. Raschety na prochnost' (In the Collection Strength Calculations) No 8, Moscow Mashgiz 1962. pp 212-224

It is assumed that at settled creep the relation of the stress and the deformation is expressed by a step-function. The regular kinematic hypotheses of the elasticity theory on the bend of bars with great curvature are used and the constants contained in them are determined (the change of the curvature k and the radius of the neutral layer r) by two conditions of static equivalence. It is proposed to set up the solution of the resulting equations for k, r by subsequent approximations with the octogonal focus method of A. A. Popov. Detailed computations are quoted for a square cross section. The possibility is mentioned to expand the solution to non-settled creep on the basis of the equations of the creep theory (aging) suggested by Yu. N. Rabotnov.

RZh Mekhanika 12-52 Abst#120261 Mechanics/Plasticity, Creep, Soil Mechanics

CHU Po-fang

Redistribution of the Stresses in Non-Homogeneous Constructions as Effect of the Creep

Jianzhu xuebao 1961, No 1, pp 14-18

On the basis of Maslov-Apytyunyan's creep theory statically indeterminate constructions are investigated, whose materials have different modulus of elasticity and degree of creep. A case of old concrete is investigated (the degree of creep does not depend on age) and an exponential function is taken as core of the creep. By making use of the conditions of joint deformations one obtains a system of integral equations of the second Volterra type concerning unknown stresses. These stresses are searched for as finite total of a series of exponential time functions. In the final analysis the problem comes to a system of algebraic equations, whose amount tallies with the amount of the unknown stresses. As conclusion a series of simple examples is quoted as illustration. M. A. Zadoyan

Abst#120293 Mechanics/Elasticity and Plasticity

HSIEH Ting-i

Stability of Sand Slopes Exposed to Vibrating Movements

Sb. nauch tr. Leningr. inzb.-stroit. inst. (Collection of the Scientific Transactions of the Leningrad Institute of Construction Engineers) 1962, No 37, pp 95-106

An experimental-theoretical investigation of the influence of the parameters of vibrating movements on the dynamic stability of slopes. G. A. Geniev

1/1

...

RZh Mekhanika 12-62 Abst#120309 Mechanics/Elasticity and Plasticity

YERSHOV V. A. HSIEH Ting-i

Slip Resistance of Water Saturated Sands as Function of the Acceleration of Vibrations

"Osnovaniya, fundamenty, mekhan, gruntov. Dokl. 20 Nauchn, konferentsii Leningr. inzh. stroit. in-ta" (Foundations, Fundamentale, Soil Mechanics. Report of the 20th Scientific Conference of the Leningrad Institute of Construction Engineers) Leningrad, 1962, pp 20-23

The results are quoted of the measurements of the slip resistance of water saturated sand which has been submitted to harmonic vibrations. The tests prove that the function of the slip resistance \mathcal{C}_a at an acceleration $\mathcal{C} \gg \mathcal{C}_0$ is expressed by the formula

$$T_a = T_0 \exp \left[-k(\alpha - \alpha_0)\right]$$

where T_0 is the slip resistance under static conditions; α_0 is the value of acceleration where $T = T_0$; k is a constant not depending on the den-

Abet#120309 (cont'à)

sity of the sand and on the load. The acceleration α_0 illustrated by a graph is a function of the latters. $K=0.003-0.0025~{\rm sec}^2/am$ for the tested sand. V. N. Nikolayevskiy

15/5

RZh Mekhanika 12-62

Abst#120494 Mechanics/Stebility of Constructions

SUNG Lian (-hung

Determination of the Crack Resistance of Prestressed Reinforced Elements of Rectangular Section

Jianzhu xuebao 1961, No 12 pp 31-33

[No abstract]

Abst#120475 Mechanics/Stability of Constructions

TAN Wen-t'ien

Simplest Method of Computing the Aggregate Semicircular Jacketing of a Railway Tunnel

Jianahu xuebao 1962, No 1, pp 26-27

[No abstract]

1/1

RND

2539 CSO: 3550-N